



QUADRO DE CARGAS												
C.D. Nº	CIRCUITO	PONTO DE LUZ				TOMADAS				POTÊNCIA (W)	FIAÇÃO mm²	DISJUNTOR (A)
		40w	60w	200w	250w	100w	200w	600w	2.000w			
01	-	-	4	-	-	-	-	-	-	800	6,0	20
02	-	-	4	-	-	-	-	-	-	800	6,0	20
03	-	-	4	-	-	-	-	-	-	800	6,0	20
04	-	-	4	-	-	-	-	-	-	800	6,0	20
05	-	-	4	-	-	-	-	-	-	800	6,0	20
06	-	-	4	-	-	-	-	-	-	800	6,0	20
07	-	-	-	6	-	-	-	-	-	1500	6,0	20
08	-	-	-	6	-	-	-	-	-	1500	6,0	20
09	-	-	-	6	-	-	-	-	-	1500	6,0	20
10	-	-	-	6	-	-	-	-	-	1500	6,0	20
11	-	-	-	6	-	-	-	-	-	1500	6,0	20
12	-	-	-	-	-	-	-	-	-	-	-	-
CARGA TOTAL										12.300 Watts		
CARGA TOTAL INSTALADA										12.300 Watts		
CARGA RESERVA										17.000 Watts		
CARGA TOTAL GERAL										29.300 Watts		

